

VILLA MARIN BUILDING STATISTICS

GENERAL CONTRACTOR: Cahill Constructions

ARCHITECT: T h o m a s Telfer

PROJECT MANAGER: Len Pieri

DEVELOPERS: Quail Hill Retirement Residences

FACTS:

Construction was completed in 18 months.

There were 27 subcontractors.

Over 200 men worked at the peak of construction.

420,000 square feet of building occupies 6 acres, with surrounding 15 acres.

Exterior walls contain 2 layers of sheet rock insulation, 2 inches of foam insulation, and synthetic plaster.

Windows are double paned.

The building sits on rock and on 129 caissons that are 3 feet in diameter and set as deep as 50 feet.

14,000 yards of concrete were poured.

There are 224 units - sized from 660 to 2,250 square feet.

The distance around the promenade deck is $\frac{2}{5}$ of a mile.

07/14/21 revised